

Room 3 – Remove Floor framing due to Visible Microbial Growth (VMG). Remove the Masonite materials from framing due to deterioration and VMG. Stud framing may need to be removed to gain access.

Foyer – Remove eighteen (18) inches of wall materials adjacent to wall Room 2 up to window frame

Room 2 – Nothing

Hallway – Remove wall materials adjacent to Bathroom

Washer and Dryer – Remove eight (8) feet of wall materials that are attached to brick wall

Bathroom – Remove raised floor and frame. Remove two (2) feet from sheetrock on wall D from the baseboard.

Room 1 – Remove ceiling materials until ceiling joist are left exposed. Remove collar material above framing. Remove insulation until the next sheetrock wall is left exposed for walls A, B C and D. Remove flooring materials until concrete is left exposed.

Kitchen – Remove flooring material until concrete is left exposed.

Living Room – Probe the two (2) by two (2) sheetrock wall as marked on the west end. Probe the one (1) by one (1) area on the column near Room 1. Remove the wooden floor material until concrete material is left exposed.